Item 6.1

# **INNOVATIVE**

ITEM NUMBER 6.1

SUBJECT Request for Gateway - Planning Proposal for land at 353A-

353C and part of 351 Church Street, Parramatta (Riverside

Theatre site)

REFERENCE F2022/01255 APPLICANT/S City of Parramatta
OWNERS City of Parramatta

**REPORT OF** Land Use Planning Team Leader

# **PURPOSE**

The purpose of the report is to seek the Parramatta Local Planning Panel's advice to Council on a request to the Department of Planning and Environment (DPE) for a Gateway Determination for a Planning Proposal for the land at 353A-353C Church Street and part of 351 Church Street, Parramatta (Riverside Theatre site).

### RECOMMENDATION


The Parramatta Local Planning Panel consider the following Council Officer recommendation in its advice to Council:

- (a) That Council approve, for the purposes of seeking a Gateway Determination from the Department of Planning and Environment, the Planning Proposal at Attachment 1 for the land at 353A-353C Church Street and part of 351 Church Street, Parramatta (Riverside Theatre site) which seeks the following changes to the Parramatta Local Environmental Plan 2011:
  - 1. increase the Maximum Height of Building (HOB) from 15m to 28m;
  - introduce a Site-Specific Clause that prevents new development generating any additional overshadowing to the Parramatta River Foreshore between 12pm and 2pm; and
  - 3. requires active street frontages.
- (b) That the Planning Proposal be forwarded to the Department of Planning and Environment for a Gateway Determination, requesting no public exhibition process for the following reasons:
  - 1. to support the efficient processing of the Planning Proposal and the redevelopment of the Riverside Theatre;
  - the CBD PP publicly exhibited controls sought a greater building height, than the subject Planning Proposal;
  - 3. the subject Planning Proposal seeks to implement the amenity controls from the CBD PP.
- (c) That Council advise the Department of Planning and Environment that the CEO will be seeking to exercise its plan-making delegations for this Planning Proposal, as authorised by Council on 26 November 2012.

Item 6.1

(d) Further, that Council delegates authority to the CEO to correct any minor anomalies of a non-policy and administrative nature that arise during the planmaking process.

### PLANNING PROPOSAL TIMELINE



### SUMMARY

- 1. The Riverside Theatre is a critical anchor performing arts facility located within the Parramatta CBD. Constructed in 1988, the current Riverside Theatre building is not fit for purpose to serve the growing community.
- 2. The redevelopment of the Riverside Theatre to deliver a modernised and expanded performance space is an important infrastructure priority reflected in Council's Cultural Plan.
- 3. Council has progressed with the preparation of a visioning document, concept reference design, and committed funding to redevelop the theatre.
- 4. The Council endorsed Parramatta CBD Planning Proposal (CBD PP) with regard to this site, among a number of things, sought to increase the height control. This change would enable the redevelopment of the theatre in line with the vision of Council. The concept design was prepared in response to the planning controls within the Council endorsed CBD PP.
- 5. However, the Department of Planning and Environment deferred the area north of the river from the CBD PP during its finalisation and retained the current height control for this site. The current height control does not enable the redevelopment of the site consistent with the concept reference design.
- As a result, a site-specific Planning Proposal is needed to implement the necessary height control to allow for the concept design and redevelopment project to progress.

Item 6.1

- The Planning Proposal found in Attachment 1 should progress for the following reasons:
  - To ensure the necessary planning controls are in place to allow the timely progression and redevelopment of the Riverside Theatre.
  - Waiting for a future review of the land north of the Parramatta River (which is subject to funding being provided by the State Government, is anticipated to commence in 2023 and which would take two to three years to complete) would cause delays to the progression of the Council prepared concept design for the Riverside Theatre.
  - The increase in HOB from 15m to 28m is considered a modest increase (particularly given the current theatre has building elements at 25m) and the 36m building height currently permitted for sites immediately east of the Theatre Site means the 28m height proposed is not out of context with existing controls in the precinct.
  - No change is sought to the existing FSR control.
  - The Site-Specific Clause implements the intent of the solar access protection plane and active frontage controls within the CBD PP.
  - The resulting building controls are considered to have an inconsequential impact on amenity, overshadowing, and overall bulk and scale; and is lower in height than the building height that would have resulted from the Council adopted CBD PP.
- 8. **Table 1** compares the existing planning controls, proposed controls under the CBD PP as endorsed by Council, the proposed controls within the Planning Proposal, and the existing building height for reference.

Control	PLEP 2011 (existing controls)	Council adopted CBD PP	Planning Proposal	Existing building
Zoning	B4 Mixed Use	B4 Mixed Use	B4 Mixed Use	B4 Mixed Use
Height	15m	Height not nominated – solar access control would allow heights of 50-60m on parts of the site.	28m	25m
FSR	3:1	3:1	3:1	Unknown

**Table 1** - Summary of existing and proposed controls

# SITE DESCRIPTION

9. The Planning Proposal applies to the land at 353A-353C Church Street (Lot 2 DP 740382) and part of 351 Church Street, Parramatta (Lot 1 DP 740382) (the site). The site is bound by Marsden Street to the west; Market Street to the north; Church Street to the east; and the Parramatta River Foreshore to the south (see Figure 1). The site has an approximate area of 7,000sqm.

Item 6.1

- 10. The site is the location of the Riverside Theatre, which is owned and operated by the City of Parramatta Council (Council). The existing building is located on the eastern side of the site, with a frontage to Church Street and the river foreshore. The building contains three separate theatres and event spaces. Above-ground parking is located on the western side of the site on the corner of Market and Marsden Street.
- 11. Prince Alfred Park is located to the north of the site and plays an important contribution to open space within the Parramatta CBD. The Old King's Parade Ground is located to the west and contributes to Parramatta's unique heritage and river setting. The land to the east of the site on Church Street is developed with approximately 5-6 storey mixed use developments. Land to the south of the site on the opposite side of the river is being redeveloped for a 192m mixed use tower (i.e. 'The Lennox' development).
- 12. The site is within walking distance to the Parramatta Light Rail stop located at Prince Alfred Square which is currently under construction as part of Stage 1 of the project.

Item 6.1




Figure 1 - Site subject to the Planning Proposal

# **EXISTING PLANNING CONTROLS**

- 13. Under the provisions of the Parramatta Local Environmental Plan 2011, the following planning controls apply:
  - B4 Mixed Use zone;
  - Maximum Height of Building control of 15 metres; and
  - Maximum Floor Space Ratio (FSR) of 3:1.
- 14. The site itself is not heritage listed; however, it is adjacent to the following heritage items projected under Schedule 5 of the PLEP 2011:
  - Lennox Bridge (State Heritage Item 100750)
  - Alfred Square (and potential archaeological site) (Local Heritage Item I686)

Item 6.1

- Marsden Rehabilitation Centre (and potential archaeological site) (State Heritage Items I00826 and I00771)
- 15. Other controls relating to flooding and Acid Sulphate Soils are described and mapped in Part 4 of the Planning Proposal in **Attachment 1**.

#### **BACKGROUND**

### **Riverside Theatre Redevelopment**

# Role of the Riverside Theatre

- 16. The Riverside Theatre is a significant cultural and performing arts venue attracting more than 180,000 patrons to 1,000 performances and events every year. For nearly three decades, the Riverside Theatre has been a critical 'anchor' cultural arts asset serving the growing population of Parramatta and Greater Sydney.
- 17. The provision and expansion of cultural infrastructure is critical in delivering Parramatta as a livable, sustainable, and productive place for the current and future populations of both the City of Parramatta and the Greater Sydney Region. However, the historical imbalance of cultural investment across Greater Sydney presents a challenge for Parramatta to achieve rounded growth and fulfill its role as the Central River City.
- 18. By 2036 the City of Parramatta will be home to an additional 150,000 people; and the Parramatta CBD will host 20,000 more residents and 83,000 more workers. This growing population and the historic lack of state government investment in cultural infrastructure in Greater Sydney is placing significant pressure on the capacity limitations of the ageing Riverside Theatre.
- 19. The redevelopment of the Riverside Theatre to modernise its infrastructure and increase its capacity is a leading priority to support the growing population of both Parramatta and Greater Sydney.

### Riverside Theatre Redevelopment Project

- Council's 'A Cultural Plan for Parramatta's CBD 2017-2022' (Cultural Plan)
  recognises the important contribution the Riverside Theatre plays in
  Parramatta's cultural identity and identifies the redevelopment of the theatre as
  a leading community priority.
- 21. The current Riverside Theatre building and facilities:
  - do not satisfactorily meet current or expected future demand;
  - do not have a positive and interactive relationship with Church Street, the new Parramatta Light Rail, or the eastern view of the river towards the MAAS development site;
  - space restrictions which limit what populist and commercially viable events can be attracted; and overall
  - does not support Parramatta's transformation into a City enriched by its culture and creativity.

Item 6.1

22. Key milestones and decision making of Council in relation to the redevelopment project are included below in **Table 2**.

Date	Milestone	Description
26	Council	Council adopted the 'Reimagining
November	adoption of	Riverside' visioning document to
2018	'Reimagining	commence the redesign process and
Council	Riverside'	provide a clear vision for the theatre in its
Meeting	visioning	role as a hub of performance excellence
	document	that attracts talent and investment.
December	Project scoping	Council considered a Joint Venture
2019 – June	, ,	redevelopment proposal in 2018-9 with
2021		Create NSW but ultimately withdrew from
		the process with an internal Council
		project team then established to re-scope
		alternative Council led schemes between
		January and February 2021.
15 June	Council	Council endorsed the Parramatta CBD
2021	endorses the	Planning Proposal (CBD PP) to be
Council	Parramatta CBD	submitted to the Department of Planning
Meeting	Planning	and Environment for finalisation following
	Proposal to be	the public exhibition process held from 21
	submitted to	September to 2 November 2020.
	Department of	
	Planning and	The Council endorsed CBD PP included
	Environment for	changes to the building height control for
	finalisation	the Riverside Theatre site.
		More detail on the CBD PP is included
		below under 'Parramatta CBD Planning
		Proposal'.
00 1 1 0004		T. D T D
26 July 2021	Council	The Riverside Theatres Redevelopment
Council	considers the	Concept Proposal was presented to
Meeting	Riverside	Council and addressed the core elements
	Theatres	of the 'Reimagining Riverside' visioning
	Redevelopment	document.
	Concept	Council resolved to progress the payt
	Proposal, and resolves to	Council resolved to progress the next stages of the concept proposal
	prepare concept design and	development, which was to explore concept design options, develop functional
	budget	specifications, and validate cost estimates.
	commitments.	Specifications, and validate cost estimates.
	Communication.	Financial decisions were also made by
		Council at this meeting, including funding
		be committed to engaging specialist
		consultants to undertake the work required
		to progress the development of the
		Concept Proposal.
		' '

Item 6.1

9 May 2022 Council Meeting	Council approves concept design and validation work, and resolves to progress to	Council approved the concept proposal validation work for the redevelopment of Riverside Theatres, which included a concept reference design and functional aspirations, and approved for the Riverside Theatre Redevelopment Project team to proceed with the development of a
	detailed business case and funding commitments.	detailed business case, project plan and budget for Council's review.  Council committed to preparing for the launch of a Design Competition process to ensure the future architectural design delivers a world class building.
		Council also noted the project has a preliminary cost estimate of \$175.4M, and approved a funding strategy to allow the project to proceed.

Table 2 – Key milestones in Riverside Theatre Redevelopment Project

23. Timeframes have also been assigned to funding allocations, and the Riverside Theatre Redevelopment Project team are progressing with a detailed business case and preparing for the next key milestones of the project, including the Design Excellence Competition.

# Riverside Theatre Concept Reference Design

- 24. As outlined in **Table 2**, a concept reference design was adopted by Council on 9 May 2022. This concept reference design explored the building envelope needed to deliver on Council's functional aspirations for the redevelopment of the Riverside Theatre, whilst responding to the draft planning controls contained within the Council endorsed Parramatta CBD Planning Proposal (see 'Parramatta CBD Planning Proposal' for more detail).
- 25. The concept reference design includes a hybrid redevelopment scheme with heights varying from approximately 13m along the riverfront and 28m towards Market Street. The concept includes the retention and upgrade of a portion of the existing facility (primarily the 700-seat riverside space) and demolishes the remainder of the existing site to construct a new state-of-the-art multi venue arts centre that fully integrates with the retained and upgraded theatre elements.
- 26. The concept reference design will be used as the basis for future detailed architectural design work, with the final detailed design being determined as part of a Design Excellence Competition process.
- 27. Figures 2 5 show the indicative building envelope from multiple perspectives, noting that the next phase of the redevelopment project will further embellish design features, building articulation, and integration with the public domain along the river foreshore. The perspectives are to provide Council and the community with an indicative form only.

Item 6.1



Figure 2 – Concept design render looking north-east from Marsden Street bridge, Parramatta



**Figure 3** – Concept design render looking north-west from Lennox bridge, Parramatta

Item 6.1



**Figure 4** – Concept design render looking south-west from corner of Church Street and Market Street, Parramatta



**Figure 5** – Concept design render looking southeast from corner of Marsden Street and Market Street, Parramatta

# Parramatta CBD Planning Proposal

# Background

- 28. Initiated in 2013, the Parramatta CBD Planning Proposal (CBD PP) was a Council led planning proposal to support Parramatta's transform as Sydney's Central City.
- 29. The CBD PP proposed changes to the land use mix and built form controls within the PLEP 2011 to deliver 46,000 new jobs and 15,000 new dwellings over the next 40 years. New controls to support this growth and protect key elements that make a city liveable, sustainable, and productive were also proposed.

Item 6.1

# Parramatta CBD Planning Proposal (as endorsed by Council on 15 June 2021)

- On 15 June 2021, Council endorsed the CBD PP to be submitted to the Department of Planning and Environment (DPE) for finalisation following the public exhibition process held from 21 September to 2 November 2020. The Council endorsed CBD PP included the land north of the river (i.e. North Parramatta)
- 31. The CBD PP proposed changes to the built form controls across the North Parramatta precinct (including the Riverside Theatre site). These changes were informed by specialist studies pertaining to urban design and heritage to help deliver appropriate built form outcomes that allow for new development whilst limiting additional overshadowing to key public spaces (including the Parramatta River Foreshore) and that achieved a suitable transition to sensitive areas such as Heritage Conservation Areas and Prince Alfred Park.

### Parramatta CBD Planning Proposal (as finalised by DPE on 6 May 2022)

- 32. On 6 May 2022, DPE finalised the CBD PP via the making of Amendment No 56 to the Parramatta Local Environmental Plan 2011. The new provisions are not due to take effect until 14 October 2022 to allow for the draft Parramatta CBD Local Infrastructure Contributions Plan to be finalised.
- 33. As part of the finalisation process, DPE made some key policy changes to the CBD PP as adopted by Council on 15 June 2021. The policy change most relevant to the Riverside Theatre site was the removal of the land north of the Parramatta River (i.e. North Parramatta) from the CBD PP with the existing land use and built form controls to be retained.
- 34. The redevelopment of the Riverside Theatre as per Council's concept design was contingent on the Council endorsed version of CBD PP being finalised. The Council adopted CBD PP established the height control needed to redevelop the theatre in line with the vision of Council the removal of North Parramatta from the CBD PP by DPE puts the development timetable at risk.
- 35. Council considered its position on the changes made to the Council endorsed CBD Planning Proposal when the Minister finalised the plan at its meeting of 25 July 2022. The portion of the Council resolution relevant to North Parramatta and the subject site reads:-

### "North Paramatta

- (d) That Council write to the Minister for Planning and the Department:
  - (1) Seeking funding for a Study for North Parramatta that incorporates urban design, heritage and economic analysis and additional temporary staff to manage the project (estimated at up to \$500,000).
  - (2) Advising that Council will not commence the Study until confirmation of funding and in-kind support has been provided.
  - (3) Seeking advice on how Council manage any new SSPPs lodged for sites north of the river prior to completion of the Study and associated plan amendment.

Item 6.1

#### **EXCEPTIONS**

- (e) Further, that Council note that new SSPPs for sites within any part of the CBD that do not:
  - 1 seek any increase in FSR, or
  - 2 seek to amend other planning controls that are being considered in the SEPP process(es) described in (c) above

will be processed by Council (examples include proposals for minor changes in height with no increase in FSR or changes to parking rates or land reservation acquisitions)."

36. The subject Site Specific Planning Proposal meets the criteria to be considered as an exception. Proceeding with this Planning Proposal ahead of the work proposed to review the controls for North Parramatta is consistent with Councils 25 July 2022 resolution.

# **DESCRIPTION OF PLANNING PROPOSAL**

- 37. The Planning Proposal seeks the following amendments to the PLEP 2011:
  - a. Increase the Maximum Height of Building (HOB) from 15m to 28m.
  - b. Introduce a Site-Specific Clause that:
    - prevents new development generating any additional overshadowing to the Parramatta River Foreshore;
    - ii. requires active street and river frontages.
- 38. No changes are proposed to the land use zoning or FSR controls.

#### PLANNING PROPOSAL ASSESSMENT

39. The following section details Council's assessment of the Planning Proposal based on strategic merit and site-specific planning issues. The Planning Proposal detailed in **Attachment 1** provides a full assessment of the proposal's consistency against relevant State Planning Policies and Ministerial Directions.

# **Strategic Merit**

- 40. The redevelopment of the Riverside Theatre, as facilitated by this Planning Proposal, aligns with the overarching policy position across state and local planning frameworks to deliver a '30-minute city' where people can live, work, and recreate within 30 minutes of their home; and to deliver cities that are productive, livable, and sustainable.
- 41. The Planning Proposal will enable the efficient redevelopment of critical cultural infrastructure that service the local and broader communities. The expanded and diversified cultural offering will support the Parramatta CBD as a destination for entertainment, will help reduce the need for travel to the Sydney CBD, the eastern harbour city.

Item 6.1

42. As detailed in **Attachment 1**, Council officers consider the Planning Proposal to be aligned with key state policies including the Greater Sydney Region Plan and the Central City District Plan; and key local policies including the Local Strategic Planning Statement, Cultural Plan, Community Infrastructure Strategy, and Parramatta CBD Planning Strategy.

# **Urban Design**

### Height

- 43. The Planning Proposal seeks an increase in height to provide a more flexible and appropriate building envelope that will enable the design concept for a modernised theatre, fit for purpose and demand, to be achieved.
- 44. **Figure 6** shows the existing height map from the Parramatta LEP 2011. The increase in height from 15m to 28m is considered a suitable increase in context of the current permitted height of 36m on the eastern side of Church Street. The increase in 28m would result in a gradual stepping down of heights moving west, and as explained within this report, is a modest increase considering the site has existing building elements at 25m.
- 45. In addition, **Figures 2 5** above show the intended building envelope of the concept design the Planning Proposal seeks to deliver. As seen in these figures, the concept design is for a building with taller and shorter elements across the site. In essence, the future built form will not result in a consistent 28m height across the site. The variation in height expression further demonstrates the low impact of the height increase.



Figure 6 - Existing height map from the Parramatta LEP

Item 6.1

### Floor Space Ratio

- 46. No changes are sought to the FSR control (i.e. density), therefore, the change will not result in greater yield than what is already permitted on the subject site. The Planning Proposal strictly addresses the envelope constraints of the current site in accommodating key theatre design elements (such as the fly tower) and deliver an upgraded theatre suitable for a diverse range of performing arts.
- 47. In addition, the prepared concept design that the Planning Proposal seeks to facilitate, has a Gross Floor Area (GFA) (for FSR calculation purposes) of approximately 10,000sqm. This is less than half of the GFA permitted on the site under the existing FSR of 3:1.

# Overshadowing

- 48. The increase in HOB to 28m is considered a modest increase (particularly given the current theatre has building elements at 25m); and would deliver a height less than what would have been permitted under the CBD PP as the Council endorsed CBD PP included changes to the building height control for the Riverside Theatre site.
- 49. Whilst the existing LEP control contains a maximum building height in metres (i.e. 15m), the CBD PP proposed that a sun access protection clause be applied to govern the distribution of height across the site.
- 50. As adopted by Council, draft Clause 7.4 'Sun access protection' (and the associated Sun Access Protection Map) required any new development on the site to be designed to prevent additional overshadowing to the southern side of the Parramatta River Foreshore between the hours of 12:00pm and 2pm.
- 51. The use of such a control would allow for the architectural design process to determine the future building height with the objective of protecting open space from additional overshadowing leading the process versus a prescribed control in metres (i.e. outcome driven design versus numerical control driven design).
- 52. Preliminary analysis by Council officers indicated that heights between 19m Relative Level (RL) at the riverfront and 60-70m (RL) at the Market St frontage could be achieved under the Sun Access Protection surface control. When the height of the sloping terrain (which approximately ranges between 4m (RL) at the riverfront and 8m (RL) at the Market St frontage) is subtracted from the RL heights an approximate measurement above ground level (existing) can be calculated. Based on the RLs above, a 15m height at ground level at the riverfront and 52-62m height at the Market Street frontage can be approximated.
- 53. The concept design included in **Figures 2-5** reflect a height of approximately 13m along the riverfront and a height of 28m towards Market Street. Using the calculations above to get an approximate measure above ground level (existing), the concept design at 28m sits comfortably underneath the solar access protection plane (including any bonus from a Design Excellence competition process).

Item 6.1

- 54. In summary, the CBD PP would have allowed for greater heights across the site (i.e. between 15m and 52-62m) and allowed for a substantially taller building envelope compared to the building envelope of the proposed concept design (where the tallest element is 28m) as shown in **Figures 2-5**.
- 55. The Planning Proposal seeks to introduce a 28m height control on the site in conjunction with a Site-Specific Clause requiring no additional overshadowing to the southern side of the Parramatta River Foreshore between the hours of 12:00pm and 2:00pm. These hours are consistent with the Council adopted policy position relating to additional overshadowing to the southern side of the river foreshore in the Council endorsed CBD PP.
- 56. It is important to acknowledge that the concept design to be delivered via the Planning Proposal exceeds the solar access protection requirements of the CBD PP by protecting solar access to the southern side of the river foreshore by an additional three hours compared to the Council adopted CBD PP. The concept design will not cause any additional overshadowing between the hours of 10:00am and 3:00pm. A series of shadow diagrams demonstrating this are included in Planning Proposal at **Attachment 1**.
- 57. Whilst the Planning Proposal will deliver greater solar access protection to the southern side of the river foreshore, for consistency with the CBD PP, the Planning Proposal seeks to retain what Council previously adopted with the draft wording for the Site-Specific Clause seeking to protect the foreshore from additional overshadowing from 12:00pm to 2:00pm.
- 58. Draft wording for the Site-Specific Clause is based on the existing Sun Access Protection clause in the PLEP 2011, and is included below:
  - Notwithstanding the maximum Height of Building control shown on the Height of Buildings Map, development consent must not be granted to development on land to which this clause applies that results in any part of a building causing additional overshadowing, on 21 June in any year, on the Parramatta River Foreshore (Lot 102 DP 1259228, Lot A DP 333263, Lot 1 DP 788637, and Lot 1 DP 1247122) between 12.00 and 14.00.
- 59. The site will also be included on the Key Sites Map to enact the Site-Specific Clause, as explained within Part 4 of the Planning Proposal in **Attachment 1**.
- 60. The concurrent application of the height control and site-specific clause is the simplest way the update the LEP to implement the intent of the CBD PP, and provide the framework needed for the Riverside redevelopment to progress.
- 61. As demonstrated in this Council Report, and in Part 3 of the Planning Proposal in **Attachment 1**, the increase in height and resulting building envelope is considered to have an inconsequential impact on amenity, overshadowing, and overall bulk and scale; and is lower than the building height that would have resulted from the Council adopted CBD PP (as explained above in Paragraph 52 54).

Item 6.1

### Active frontages

- 62. The CBD PP introduced a clause to promote uses that attract pedestrian traffic along certain ground floor street frontages, public space frontages and river foreshore frontages. An Active Frontages Map identified the streets where active frontages were required, and therefore where the clause applied.
- 63. The site's street frontages of Church, Market, and Marsden Street were included on the Active Frontages Map (as endorsed by Council). However, DPE's removal of North Parramatta from the finalised CBD PP has resulted in the active frontage clause not applying.
- 64. For consistency with the Council endorsed CBD PP, a site-specific clause requiring active frontages is also proposed to ensure the ground floor of the future development engages with the surrounding streets and public domain. This will also need to be responded to as part of a future Design Excellence process.

# Design Excellence

65. A Design Excellence Competition will be facilitated to guide the detailed reference design process for the site. The concept design will be used as the basis of the future design process. A 15% FSR bonus can be awarded to the winning design, bringing the maximum permitted height from 28m to 32m (i.e. 28m + 15%), which is still well below the height that could have been achieved if the CBD PP was finalised as adopted by Council.

# Heritage

- 66. As outlined above under 'Existing Planning Controls', the site is adjacent to local and state heritage items including Lennox Bridge, Prince Alfred Square, and Marsden Rehabilitation Centre. These items were carefully considered as part of the specialist heritage studies completed as part of the preparation of the CBD PP.
- 67. These studies were carried out to help inform a suite of planning controls to allow renewal and some intensification of development, whilst still achieving a suitable transition to sensitive areas such as Heritage Conservation Areas and Prince Alfred Park and limiting additional overshadowing to key public spaces (including the Parramatta River Foreshore).
- 68. Specifically, the Hector Abraham heritage study of the interface areas for North Parramatta and the riverbank did not raise objection, or recommend any changes, to the application of the Solar Access Protection control and the likely resulting heights for the Riverside site when assessing the impact of the proposed controls on heritage values. This work formed part of the CBD PP package endorsed by Council on 15 June 2021 and sent to the DPE for finalisation in July 2021.

Item 6.1

- 69. As the concept reference design has responded to the Solar Access Protection control of the CBD PP, the heritage assessment undertaken as part of the CBD PP is considered applicable and transferrable for this Planning Proposal.
- 70. As the concept design would deliver a height less than what the CBD PP could have delivered, Council officers consider the proposal to have even less of an impact on the surrounding area and heritage context. In addition, as discussed under 'Urban Design', the proposed height of 28m presents a modest increase given there are existing building elements at 25m, further limiting the heritage implications of the planning proposal.
- 71. Whilst the Planning Proposal is considered acceptable from a heritage perspective as outlined above, the Design Excellence process will need to respond to the unique heritage and archaeological context of North Parramatta and Old Government House to ensure the heritage values of the city continue to be celebrated and protected.

# **Flooding**

- 72. Reflective of the site's location adjacent to the Parramatta River, the site is flood affected. The entire site is located within the Probable Maximum Flood for the Upper Parramatta River, and the western side of the site is affected by the 100 year flood event
- 73. As detailed within this report, the Planning Proposal does not seek any changes to the FSR control (therefore, the change will not result in greater yield than what is already permitted on the subject site).
- 74. As the Planning Proposal is not intensifying development yield, and strictly addressing urban design considerations through the alteration of building height, Council officers consider this Planning Proposal to be consistent with Ministerial Direction 4.1: Flooding (that sits under Direction Focus Area 4: Resilience and Hazards).
- 75. Any future development on the site will need to respond to the Flood Risk Development Manual and the relevant controls contained within the PLEP 2011 and the Parramatta Development Control Plan 2011.

# **PLAN MAKING DELEGATIONS**

- 76. Plan making delegations were announced by the then Minister for Planning and Infrastructure in October 2012 allowing councils to make LEPs of local significance. On 26 November 2012, Council resolved to accept the delegation for plan making functions, and for these functions be delegated to the Chief Executive Officer.
- 77. It is recommended that Council request to the Department of Planning and Environment to exercise its plan making delegations for this Planning Proposal. This means that after the Planning Proposal has received a Gateway Determination, complied with any conditions (including any requirements for public exhibition), Council officers can deal directly with the Parliamentary Counsel on the legal drafting and finalisation of the amendment to the LEP facilitated by this Planning Proposal.

Item 6.1

78. This will support the efficient processing of the Planning Proposal, and in turn, the redevelopment of the Riverside Theatre. Council officers consider this suitable due to the nature and unique context of the change which are of local significance.

#### FINANCIAL IMPLICATIONS FOR COUNCIL

- 79. As discussed within **Table 2**, the redevelopment of the Riverside Theatre has spent Council monies in preparing the concept design and validation work. Council has also allocated funding to the delivery of the project.
- 80. Should Council wait for any future precinct wide review of North Parramatta, the project will be stalled, and considerations will need to be made in relation to the committed funds.
- 81. The Planning Proposal will help ensure the efficient progression of the redevelopment process, and the use of the committed funds to deliver this critical piece of infrastructure for the City of Parramatta.

### **CONCLUSION AND NEXT STEPS**

- 82. Council officers recommend Council endorse the Planning Proposal in **Attachment 1** to ensure the necessary planning controls are in place to allow the timely progression and redevelopment of the Riverside Theatre.
- 83. It is recommended that Council endorse, and forward, the Planning Proposal in **Attachment 1** to the Department of Planning and Environment for a Gateway determination.
- 84. It is also recommended that Council request no public exhibition process to enable the efficient processing of the Planning Proposal. This is because the CBD PP exhibited controls to allow greater building heights, and as this Planning Proposal seeks a lower height and implements the amenity controls from the CBD PP, a public exhibition process is not considered necessary.

Sonia Jacenko

Land Use Planning Team Leader

Robert Cologna

Group Manager, Strategic Land Use Planning

Jennifer Concato

**Executive Director City Planning and Design** 

### ATTACHMENTS:

Planning Proposal - Land at 353A-353C Church Street and part of 351 Church Street, Parramatta (Riverside Theatre Site) 53 Pages

### REFERENCE MATERIAL